



| Item | Code | Description | Qty | Material | Unit Mass |
|------|----------------------|--|-----|--|-------------|
| 11 | ISO 4017 - M8 x 16 | Hexagon head screws | 12 | Cl 10.9 ISO 898 Galvanized | 0,012 kg |
| 10 | ISO 7089 - 8 | Plain washers | 12 | HV 200 ISO 7980 Galvanized | 0,002 kg |
| 9 | ISO 4017 - M20 x 120 | Hexagon head screws | 56 | Cl 10.9 ISO 898 Galvanized | 0,366 kg |
| 8 | ISO 7089 - 20 | Plain washers | 56 | HV 200 ISO 7980 Galvanized | 0,017 kg |
| 6 | 7110-000-03-00 | Protection 03 for strip encoder | 1 | Welded construction steel S355J0 EN10027 | 0,628 kg |
| 5 | 7110-000-02-00 | Protection 02 for strip encoder | 1 | Welded construction steel S355J0 EN10027 | 0,628 kg |
| 4 | 7110-000-01-00 | Protection 01 for strip encoder | 2 | Welded construction steel S355J0 EN10027 | 0,692 kg |
| 3 | 06-08-23-AF | AZ Bearing ROLLIX - Groupe De Fontaine | 1 | | 202,000 kg |
| 2 | 7113-000-00-00 | AZ Fork | 1 | | 3419,667 kg |
| 1 | 7111-000-00-00 | Base structure | 1 | | 1796,654 kg |

| | | | | | |
|---|--|--|--|--|--|
| | | EIE GROUP via Torino 151A - Mestre Venezia - 30172 - ITALY tel. +39 041 5317906 - www.eie.it | | | |
| Material: | | Surface: | | Tolerances according to: ISO 2768-1-m ISO 2768-2-k | |
| Status: | | Mass: 5442,61 kg | | Roughness: Compressa/Job no.: G0113 | |
| | | Date: 23/12/2013 | | Scale: 1:20 | |
| | | Designed: AC | | Naming: Electro Mechanics Mount Assembly | |
| | | Checked: AB | | | |
| | | Approved: GPM | | Drawing N.: 7110-000-00-00 | |
| A | | Sheet: 1/1 | | Drawing size: A1 | |
| ALL RIGHTS BELONG TO EIE GROUP S.p.A. NO COPIES, REPRODUCTION OR DISSEMINATION ARE PERMITTED. | | Filename: Mount Assembly.iam | | | |